



DEPARTMENT OF PUBLIC WORKS
 Maple Street Annex
 725 Maple Street - PO Box 100
 Hillsboro, Missouri 63050
 (636)797-5340 – www.jeffcomo.org

Last Updated: **Thu Sep 14, 2023** 

PUBLIC INFORMATION SHEET

- | | | |
|---|-------------------------------------|---------------------------------------|
| 1. Project Identification: | Mount Olive Road Bridge Replacement | |
| | STP-5444(601) | |
| 2. Resident Engineer: | Robert Russell | |
| 3. County Representative: | Robert Russell | 636.797.5342
RRUSSELL@JEFFCOMO.ORG |
| 4. County’s Consultant: | ABNA | |
| 5. Council District(s): | 6 | |
| 6. Approximate Date for Approved Final Plans: | Fall | 2023 |
| 7. Additional Right-of-Way Required?: | Yes | |
| 8. Approximate Date of Right-of-Way Acquisition: | Fall | 2023 |
| 9. Length of Road or Bridge Project: | .13 | Miles |
| 10. Existing Bridge Rating and Load Posting: | 40.5% | 30TON |
| 11. Contract Amount: | \$1,089,945.50 | |
| Low Bid?: | Yes | |
| Funding Source: | 80% Federal | 20% Local |
| 12. Contractor: | Joe's Bridge & Grading | |
| 13. Contract Performance Period: | 12/31/2024 | Completion Date |
| 14. Estimated Construction Start Date: | Winter | 2023 |
| 15. Estimated Construction Completion Date: | Winter | 2024 |

16. Project Details:

The proposed plan calls for NU 35 (900), Pre-stressed Concrete NU-Girders with a concrete slab on top. There will be roadwork to tie the bridge back into the roadway. The end bents will be constructed on H piles. The abutments and disturbed creek channel will be lined with heavy stone revetment. The bridge will include twelve-foot lanes, four-foot shoulders and concrete barrier curbs.

[Preliminary Plans](#)