



DEPARTMENT OF PUBLIC WORKS
Maple Street Annex
725 Maple Street · PO Box 100
Hillsboro, Missouri 63050
(636) 797-5340

Last Updated: 6/26/2020

PUBLIC INFORMATION SHEET

1. **Project Identification:** Seckman Road @ Mastodon State Park Entrance
Safety Proejct
STP-7202 (604)
2. **Resident Engineer:** J.R. Hamilton
3. **County's Representative:** TBD
4. **County's Consultant:** TWM Engineers
5. **Council District:** District 4
6. **Approximate Date for Approved Final Plans:** Fall 2021
7. **Additional Right-Of-Way Required:** Yes
8. **Approximate Date of Right-Of-Way Acquisition:** Fall 2020
9. **Length of Road or Bridge:** 0.56 Miles
10. **Bridge Rating and Load Posting:** N/A
11. **Contract Amount:** TBD
Low Bid: TBD
Funding: 70% Federal / 30% County
12. **Contractor:** TBD
13. **Number of Working Days:** TBD
14. **Estimated Construction Starting Date:** Spring 2022
15. **Estimated Completion Date:** Spring 2022
16. **Miscellaneous Information** (location, description of work, detour roads, utilities relocation, message boards, shoulder width, etc.):

Re-aligning portions of Seckman Road with a new horizontal and vertical alignment to provide for adequate sight distances, adding 8' paved shoulders to the South Side of Seckman Road, while also adding curb and gutter sections on the North Side of Seckman Road, along with adding a closed drainage system. New striping and signage is also included within the project. This project will allow for connectivity between the many nearby subdivisions to access the Mastodon State Park amenities.