



PUBLIC INFORMATION SHEET

1. **Project Identification:** Seckman Road Phase 1 - Round About & Pedestrian Improvements
STP-7202 (602)
2. **Resident Engineer:** J.R. Hamilton
(636) 797-5340
3. **County's Representative:** John May
4. **County's Consultant:** HDR
5. **Council District:** Council District 4 - Charles Groeteke
6. **Approximate Date for Approved Final Plans:** Summer 2020
7. **Additional Right-Of-Way Required:** Yes - Approx. 0.3 Acres
8. **Approximate Date of Right-Of-Way Acquisition:** 2019
9. **Length of Road or Bridge:** 0.33 Miles
10. **Bridge Rating and Load Posting:** N/A
11. **Contract Amount:** \$1,699,441.55
Low Bid: Yes - of 4 Bidders
Funding: 20% Local - 80% Federal
12. **Contractor:** Gershenson Contruction
13. **Number of Working Days:** 145 for Phase 1 & 2 Combined
14. **Estimated Construction Starting Date:** July 2021
15. **Estimated Completion Date:** Spring 2022
16. **Miscellaneous Information** (location, description of work, detour roads, utilities relocation, message boards, shoulder width, etc.):

The project includes reutilization of the existing 65+ feet of pavement by restriping two 11 foot lanes, 6" concrete islands, 5-7 foot wide shoulders , a 6" curb on the backside of the shoulder/ bike lane protecting a 5 foot wide pedestrian sidewalk with ADA compliant curb ramps, construction of a roundabout at the intersection of Old Lemay Ferry Road and an Signalized Intersection at Seckman Middle School.